



AUSTRALIAN RAIL TRACK CORPORATION LTD

Southern Sydney Freight Line IMPORTANT COMMUNITY INFORMATION

Sefton and Birrong Area Weekend Works

Australian Rail Track Corporation (ARTC) will be undertaking construction works in your area over the weekend of 14th to the 16th November 2009. These works are part of the construction of the Southern Sydney Freight Line (SSFL). In this area, there will be work across six sites as below:

Site One: Sefton Triangle (works in the corridor from Cooper Road to Auburn Rd) – The work will begin at 8.00am and continue until 6.00pm on both Saturday and Sunday. The works will involve the construction of new overhead wiring, bonding and replacement of overhead wiring components under the footbridge and installing new power poles and string new conductors across track.. The equipment used at this site will be hi-rail cherry pickers, 25 ton slew crane, pole truck, NDD truck and light trucks with hand tools and cable.



Site Two: Sefton Dive (within rail corridor from Cooper Rd to Auburn Rd) - The work will begin at 7.00am and continue until 6.00pm on both Saturday and Sunday. The works will involve excavations near the track. The equipment used will be a hand held portable grinder, crow bar, hammer and other hand tools. They will also be carrying out Thermit welding.

Site Three: Sefton Station (these works are located at the station): The works will begin at 6.00am and continue until 10.00pm on Saturday and on Sunday it will begin at 8.00am and continue until 10.00pm. The works will involve partially barricading Sefton platform below area of works, installing rails to new down side stairs, assemble screens on new down side stairs, assembling high throw screens and installing porch columns, frames and roof. The equipment used will be crane, scaffold and scissor lifts.



Site Four: Birrong (works on Service Bridge at Auburn Rd) – The works will begin at 7.00am and continue until 6.00pm on both Saturday and Sunday. The works will involve attaching the water main to the Auburn Road service bridge. The equipment used will be a crane, hi-rail truck, elevated work platforms and hand tools.



Site Five: Sefton (Woods Road underbore) – the works will begin at 7.00am on Saturday and continue until 2.00am on Monday. The works will involve boring at the Energy Australia Undertrack Bore. The equipment used will be a directional bore, excavator, dumpy and hand tools.



Site Five: Sefton Dive Auburn Road (in the rail corridor adjacent to Wellington Rd, near Gascoigne Rd) – the works will begin at 5.00am on Saturday and continue until 6.00pm Sunday. The works will involve the track connection and traction bond. The equipment used will be an excavator, dumpy and hand tools.



We appreciate everyone's patience while we build this important project.

Further information

For further information and any enquiries, please call the 24 Hour Information and

Complaints Line 1800 182 543



Or Email ssfl@artc.com.au or visit www.ssfl.artc.com.au

Translating & Interpreting Service – Please Phone: 131 450